

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21989-00-00
Spot: NWSEWSW Sec/Twnshp/Rge: 19-13S-30W
335 feet from S Section Line, 947 feet from W Section Line
Lease Name: HOLADAY Well #: 1-19
County: GOVE Total Vertical Depth: 4619 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 W MAIN ST
SALEM, IL 62881

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		170 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/09/2013 12:00 AM
Plug Co. License No.: 33935 Plug Co. Name: H. D. DRILLING, LLC
Proposal Rcvd. from: DOUG Company: H. D. DRILLING, LLC Phone: (620) 617-6023

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 02/09/2013 5:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2325 w/25 sx
2nd plug @1375 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

RECEIVED
MAR 04 2013
KCC WICHITA

District: 04

Signed C. Morris
3/12/12 (TECHNICIAN)

MAR 18 2013