

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21696-00-00  
Spot: S2NENENW Sec/Twnshp/Rge: 36-22S-17W  
335 feet from N Section Line, 2970 feet from E Section Line  
Lease Name: BERT Well #: 1-36  
County: PAWNEE Total Vertical Depth: 4339 feet

Operator License No.: 34624  
Op Name: VICTORY OPERATING, INC.  
Address: 6 N. SCOTTSDALE  
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4130		WITH 2 SX CMT
PLG	5.5	4280	0	
PROD	5.5	4330	2655	WITH 200 SX CMT
SURF	8.625	1043		WITH 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2013 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4110' WITH 2 SX CMT. PLUG AT 1080' WITH 12 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/25/2013 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4130' WITH 2 SX CMT ON TOP OF THE PLUG. 1ST PLUG AT 1083' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 446' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4233	4239		
4160	4176		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

*Richard Mc Lacey*  
(TECHNICIAN)

RECEIVED  
JAN 31 2013  
KCC DODGE CITY

RECEIVED  
FEB 04 2013  
KCC WICHITA

*R.M.L.*