

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20952-00-02
Spot: W2NWNE Sec/Twnshp/Rge: 34-17S-27W
4637 feet from S Section Line, 2297 feet from E Section Line
Lease Name: WHIPPLE Well #: 34-2
County: LANE Total Vertical Depth: 4690 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4272 | | |
| DVT | 4.5 | 2083 | | WITH 900 SX CMT |
| PROD | 4.5 | 4689 | 0 | WITH 200 SX CMT |
| SURF | 8.625 | 299 | | WITH 225 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/27/2012 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PULL TBG TO 2000' & CIRCULATE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/27/2012 2:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4252' & PUMPED 50 SX CMT & 150# HULLS. PULLED TBG TO 2020' & PUMPED 130 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4570 | 4574 | | |
| 4220 | 4230 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

RECEIVED
JAN 14 2013
KCC WICHITA

District: 01

RECEIVED

JAN - 9 2013

KCC DODGE CITY

Signed

Michael Maier
12/27/13 (TECHNICIAN)