

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05297-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 30-11S-17W
336 feet from S Section Line, 4763 feet from E Section Line
Lease Name: PEAVEY Well #: 1
County: ELLIS Total Vertical Depth: 3653 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3653		250 SX
SURF	8.625	185		115 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2013 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 735-4621

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement; 12 sx gel; 600 # hulls.
PBTD-3606
Perforations- 3256'-3260'; 3314'-3318'; 3370'-3374'; 3498'-3503'; 3653'-3654'.
GPS: 39.06040 -099.25815
343' FSL 4749' FEL NE SW SW SW

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2013 12:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech shot 2 shot holes at 1850'-1367'-835'.
Murfin ran in hole with tubing to 3505'. Quality rigged to tubing and mixed and pumped 12 sx gel followed by 50 sx cement w/300 # hulls mixed in.
Pulled tubing to 1850'. Quality rigged to tubing and mixed and pumped 185 sx cement w/300 # hulls mixed in to circulate cement to surface.
Pulled tubing. Topped off 5 1/2" casing with 20 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 35 sx cement to pressure with 250 psi and 250 psi shut in pressure.

Perfs:


Top	Bot	Thru	Comments
3653	3654		
3498	3503		
3370	3374		
3314	3318		
3256	3260		

RECEIVED
FEB 18 2013
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 6506

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

CM

FEB 04 2013