

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-22063-00-00
Spot: NWNESWNE Sec/Twnshp/Rge: 13-15S-26W
1622 feet from N Section Line, 1920 feet from E Section Line
Lease Name: TREBOR Well #: 1
County: GOVE Total Vertical Depth: 4440 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		165 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/09/2012 12:00 AM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: CARLOS Company: H2 DRILLING LLC Phone: (620) 290-5912

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 12/09/2012 9:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @1900 w/25 sx
2nd plug @850 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

RECEIVED
JAN 22 2013
KCC WICHITA

District: 04

Signed [Signature]
[Signature] (TECHNICIAN)

JAN 17 2013