

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20925-00-01  
Spot: N2SWNE Sec/Twnshp/Rge: 28-9S-25W  
1650 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: SAUER Well #: 2  
County: GRAHAM Total Vertical Depth: 2255 feet

Operator License No.: 34392  
Op Name: TEXKAN EXPLORATION LLC  
Address: 307 NW 3RD ST PO BOX H  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	231		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2013 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TOM Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 639-5727

Proposed Plugging Method: Ordered 175 sx 60/40 pozmix 4% gel cement.  
Old dry hole well had to be drilled out and re-plugged because it fell within the area of influence of a new UIC Application.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/25/2013 2:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Drilled to 2255' to the Anhydrite.  
Ran tubing to 2253' and pumped 25 sx cement.  
Pulled tubing to 1390' and pumped 100 sx cement.  
Pulled tubing to 278' and pumped 40 sx cement.  
Pulled tubing to 60' and pumped 10 sx cement.  
  
GPS: 39.24354 -100.11457

Remarks: EXPRESS WELL SERVICE AND SUPPLY

Plugged through: TBG

RECEIVED  
JAN 31 2013  
KCC WICHITA

District: 04

Signed [Signature]  
3/04/13 (TECHNICIAN)

CM

JAN 28 2013