

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22512-00-00
Spot: W2SWSW Sec/Twnshp/Rge: 20-24S-5E
660 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BLUESTEM B (BLACKSTONE) Well #: 7
County: BUTLER Total Vertical Depth: 2709 feet

Operator License No.: 33971
Op Name: TRIPower RESOURCES, LLC
Address: BOX 849
ARDMORE, OK 73402

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2699		200 SX
SURF	8.625	212		175 SX
T1	2.375	2634		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2013 12:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: GARY REED Company: _____ Phone: (316) 321-6650

Proposed Plugging Method: SPOT 50 SX ON BOTTOM, PULL TUBING. PERF @ 262'. PLUG FROM 252 TO SURFACE.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 01/28/2013 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

1/28 TAGGED TUBING TO 2593' & SPOTTED 35 SX OF 60 X 40, 4% GEL, 3% CAL, 1/4 LB OF FLOW SEAL. TAGGED @ 2075'. TIED ONTO CASING, ESTABLISHED CIRCULATION, PUMPED 165 SX. NO RETURN ON CEMENT. PUMPED AN ADDITIONAL 60 SX AND CIRCULATED. TOPPED OFF W/15 SX.

Perfs:

Top	Bot	Thru	Comments
2586	2596	TBG	


RECEIVED
FEB 08 2013
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed


3/04/13 (TECHNICIAN)