

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20968-00-00
Spot: E2SENE Sec/Twnshp/Rge: 5-32S-39W
3297 feet from S Section Line, 337 feet from E Section Line
Lease Name: YEAGER B Well #: 3
County: MORTON Total Vertical Depth: 5975 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	39		WITH 21 SX CMT
DVT		3143		WITH 705 SX CMT
PROD	5.5	5974	0	WITH 1280 SX CMT
SURF	8.625	1733		WITH 675 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/28/2013 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 20 SX CMT WITH 200# HULLS ON BOTTOM. PLUG AT 3200' WITH 15 SX CMT. PLUG AT 1780' WITH 25 SX CMT. PLUG AT 550' WITH 25 SX CMT. PLUG AT 550' WITH 25 SX CMT. PLUG AT 40' WITH 5 SX CMT. 10 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2013 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT TO 5853'. SPACER TO 3000'. TAG WITH SLICK LINE FLOAT. PLUG AT 3000' WITH 15 SX CMT. SPACER TO 1780'. TAG WITH SLICK LINE FLOAT. PLUG AT 1780' WITH 25 SX CMT. SPACER TO 140'. PUMP 16 SX CMT FROM 140' TO 0'. PRESSURE TO 1000#. HOLDING. PUMP 3 SX CMT DOWN ANNULUS TO 500#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
5826	5853		
5808	5813		

RECEIVED
FEB 04 2013
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 UR RULE** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED

JAN 29 2013

KCC DODGE CITY

Signed

Ken Jehlik
1/28/13

(TECHNICIAN)