

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20654-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 5-25S-23W
1394 feet from S Section Line, 1583 feet from E Section Line
Lease Name: ANN Well #: 5-9
County: FORD Total Vertical Depth: 5850 feet

Operator License No.: 32204
Op Name: REDLAND RESOURCES, INC.
Address: 6001 NW 23RD ST
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3556		
CIBP		4570		WITH 2 SX CMT
COND	30	50		WITH 5 SX CMT
PC	4.5	802		WITH 400 SX CMT
PROD	4.5	4834	0	WITH 225 SX CMT
SURF	13.375	264		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2013 11:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: CHASE THOMAS Company: REDLAND RESOURCES Phone: (405) 789-7104

Proposed Plugging Method: SET CIBP @ 4600' WITH 2 SX CMT. PLUG AT 1450' WITH 30 SX CMT. PLUG AT 850' CIRCULATE CMT TO SURFACE. PRESSURE TEST 13 3/8" X 4 1/2" ANNULUS TO 500 PSIG.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2013 1:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

3/5/10: TOP OF CMT AFTER THE PORT COLLAR JOB WAS 232'. COMPANY ATTEMPTED TO PUMP DOWN THE 13 3/8" X 4 1/2" ANNULUS WHEN THE PORT COLLAR FAILED TO CIRCULATE. THEY WERE ONLY ABLE TO GET 1/2 BBL OF CMT IN IT & IT PRESSURED TO 650 PSIG. SET CIBP @ 4570' WITH 2 SX CMT. 1ST PLUG AT 1470' WITH 30 SX CMT. 2ND PLUG AT 864' WITH 96 SX CMT WHICH CIRCULATED TO SURFACE. PULLED TBG OUT OF HOLE & TOPPED OFF WITH 8 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4680	4686		
4647	4676		

RECEIVED
FEB 03 2013
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

JAN 30 2013

KCC DODGE CITY

Signed

Richard W. Lacey
2/22/13

(TECHNICIAN)

RAIT