

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20731-00-00
Spot: SWNWSWNE Sec/Twnshp/Rge: 7-25S-23W
1719 feet from N Section Line, 2347 feet from E Section Line
Lease Name: SAWLOG Well #: 7-7
County: FORD Total Vertical Depth: 4900 feet

Operator License No.: 32204
Op Name: REDLAND RESOURCES, INC.
Address: 6001 NW 23RD ST
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4510		WITH 2 SX CMT
CIBP		4600		
CIBP		4655		
DVT		1191		CMT TO SURFACE
PROD 4.5		4893	0	WITH 200 SX CMT
SURF 8.625		238		WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2013 12:30 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: CHASE THOMAS Company: REDLAND RESOURCES Phone: (405) 789-7104

Proposed Plugging Method: SET CIBP OR 25 SX CMT WITH HULLS. PLUG AT 1500' WITH 15 SX CMT. PLUG AT 1200' CIRCULATE WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2013 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4510' WITH 2 SX CMT. 1ST PLUG AT 1500' WITH 15 SX CMT. 2ND PLUG AT 1200' WITH 88 SX CMT. 3RD PLUG PRESSURED TO 500# & WOULDN'T TAKE ANY CEMENT.

8 7/8 x 4.5 annulus

Perfs:

Top	Bot	Thru	Comments
4690	4697		
4673	4697		
4606	4610		
4566	4576		

RECEIVED
FEB 04 2013
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

JAN 30 2013

KCC DODGE CITY

Signed

[Handwritten Signature]
1/24/2013
(TECHNICIAN)