

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20391-00-00
Spot: E2E2W2SE Sec/Twnshp/Rge: 13-25S-31W
1263 feet from S Section Line, 1372 feet from E Section Line
Lease Name: RENICK Well #: 1
County: FINNEY Total Vertical Depth: 2717 feet

Operator License No.: 33358
Op Name: RENICK ENERGY, L.C.
Address: 716 KENSINGTON BLVD
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2510		WITH 2 SX CMT
PROD	4.5	2680	605	WITH 200 SX CMT
SURF	8.625	556		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/28/2012 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 2500' & 2 SX CMT OR TBG TO 2500'. PLUG AT 980' WITH 80 SX CMT. PLUG AT 590' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 01/02/2013 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAK 1500'-1800'. CIBP @ 2510' WITH 2 SX CMT. BLOW A CASING COLLAR @ 975'. PIPE NOT FREE. PUMP 80 SX CMT INTO BLOWN CASING COLLAR & CASING LEAK @ 0 PSI. SDFW. TAG TOC IN 4 1/2" @ 922'. SHOOT CASING COLLAR @ 605'. PULLED 1 JOINT. SPOT 50 SX CMT AT 565'. SPOT 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
2562	2572		

RECEIVED
JAN 11 2013
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

Signed Ken Jehlik
1/2/13 (TECHNICIAN)

RECEIVED
JAN - 8 2013
KCC DODGE CITY

Handwritten mark