

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25555-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 2-16S-26W
2024 feet from S Section Line, 2195 feet from W Section Line
Lease Name: WILLIAMSON Well #: 1
County: NESS Total Vertical Depth: 4624 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/15/2013 2:30 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERN Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 2060' WITH 50 SX CMT. 2ND PLUG AT 1280' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 04/15/2013 4:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2060' WITH 50 SX CMT. 2ND PLUG AT 1280' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

APR 26 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed


5/6/13
(TECHNICIAN)

RECEIVED

APR 15 2013

KCC DODGE CITY

Form CP-2/3

Handwritten initials