

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20425-00-00
Spot: SWSWSESW Sec/Twnshp/Rge: 12-24S-30W
159 feet from S Section Line, 1649 feet from W Section Line
Lease Name: O'BRATE UNIT Well #: 1-12
County: GRAY Total Vertical Depth: 5000 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4806		WITH 2 SX CMT
CIBP		4963		
PROD	5.5	4995	2482	WITH 125 SX CMT
SURF	8.625	446		WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2013 10:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 4806' WITH 5 SX CMT. PLUG AT 1980' WITH 15 SX GEL & 50 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2013 8:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4806' WITH 2 SX CMT. SHOT COLLAR SPLIT SHOT @ 3200'. COULD NOT PULL CASING @ 70,000# (20,000# OVERSTRING WEIGHT). SHOT COLLAR SPLIT SHOT @ 2482'. PIPE FREE. 1ST PLUG AT 1974' WITH 50 SX CMT. 2ND PLUG AT 1176' WITH 50 SX CMT. 3RD PLUG AT 462' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4856	4862		

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED
MAR 26 2013
KCC DODGE CITY

Signed [Signature]
(TECHNICIAN)

ADW