

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20572-00-00  
Spot: SWNENENW Sec/Twnshp/Rge: 35-14S-19W  
4924 feet from S Section Line, 3038 feet from E Section Line  
Lease Name: AU-HERL Well #: 3  
County: ELLIS Total Vertical Depth: 3711 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3535		
PROD	5.5	3709		135 SX
SURF	8.625	1339		650 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2013 1:30 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM, LLC Phone: (316) 524-1225

Proposed Plugging Method:  
03/07/2013- Ordered 150 sx 60/40 pozmix 4% gel cement  
03/08/2013- Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Perforations: 1300' and 1850'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/08/2013 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/07/2013- Pumped 150 sx cement down tubing and out mud anchor. Pulled tubing.  
03/08/2013- Tagged cement at 2950'. Perforated 1300' and 1850'.  
Ran tubing to 2200' and pumped 100 sx cement w/150 # hulls.  
Pulled tubing to 1350' and pumped 75 sx cement and bradden head blew out.  
POOH. Fixed braden head and hooked to casing. Pumped 300 sx cement w/250 # hulls.  
Cement circulated out of braden head and into pit. Shut valve on braden head and pressured up casing to 350 psi. Shut in.

GPS: 38.79739 -099.430316

Perfs:

Top	Bot	Thru	Comments
3574	3577		
3565	3568		

Remarks: COPELAND CEMENTING AND ACID COMPANY TICKET # 38328

Plugged through: TBG

District: 04

Signed Ray A Dinkel  
4/02/13 (TECHNICIAN)

CM

RECEIVED  
MAR 18 2013

KCC WICHITA

MAR 11 2013