

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19070-00-00
Spot: SENWNW Sec/Twnshp/Rge: 20-31S-6E
4293 feet from S Section Line, 3960 feet from E Section Line
Lease Name: KEESEY Well #: 1
County: COWLEY Total Vertical Depth: 2917 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2872		
PROD	4.5	2893		90 SX
SURF	8.625	193		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2013 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/08/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 130' ABOVE PERFS @ 2700', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 547', POOH W/547' (17 JOINTS) 4-1/2" CASING. 2-8-2013, RIH W/TBG @ 350', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 2-8-2013. COPELAND CEMENT TICKET #41788.

Perfs:

Top	Bot	Thru	Comments
2830	2862	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
02/13
(TECHNICIAN)