

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23935-00-00
Spot: NENWSW Sec/Twnshp/Rge: 16-30S-7E
2305 feet from S Section Line, 4329 feet from E Section Line
Lease Name: SCHULZ Well #: 1
County: COWLEY Total Vertical Depth: 3276 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3227		250 SX
PROD	5.5	3271		100 SX
SURF	8.625	302		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2013 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM, LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/18/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE OPEN HOLE @ 3200', DUMP BAILED 5 SXS CEMENT ON TOP. 2-8-2013, RIH ON WIRELINE SHOT SQUEEZE HOLES @ 350'-351' (2 HOLES). RIH W/TBG @ 360', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 2-8-2013. COPELAND CEMENT TICKET #41790.

Perfs:

Top	Bot	Thru	Comments
3271	3276	OH	

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2013

Remarks: BACKSIDE ALREADY HAD CEMENT @ SURFACE / TA

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

12