

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23941-00-00
Spot: SESWNW Sec/Twnshp/Rge: 16-30S-7E
2953 feet from S Section Line, 4309 feet from E Section Line
Lease Name: SCHULZ Well #: 2
County: COWLEY Total Vertical Depth: 3279 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.4	3227		250 sxs
PROD	5.5	3272		100 SX
SURF	8.625	302		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2013 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM, LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/15/2013 2:35 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE OPEN HOLE @ 3220', DUMP BAILED 5 SXS CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 360'-361' (2 HOLES). 2-15-2013, RIH W/TBG @ 355', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 2:35 PM 2-15-2013. COPELAND CEMENT TICKET #41797.

Perfs:

Top	Bot	Thru	Comments
3272	3279	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 29 2013

Remarks: DENIED TA

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
4/02/13
(TECHNICIAN)

JK