

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23943-00-00
Spot: S2NESENW Sec/Twnshp/Rge: 16-30S-7E
3407 feet from S Section Line, 2996 feet from E Section Line
Lease Name: SCHULZ Well #: 4
County: COWLEY Total Vertical Depth: 3228 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| L1 | 4.5 | 2850 | | 118 SX |
| PROD | 5.5 | 3213 | | 100 SX |
| SURF | 8.625 | 302 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2013 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/08/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERFS @ 2810', DUMP BAILED 5 SXS CEMENT ON TOP. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 350'-351' (2 HOLES). 2-8-2013, RIH W/TBG @ 350', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 2-8-2013. COPELAND CEMENT TICKET #41789. 2-15-2013, TOPPED WELL OFF W/10 SXS BACK TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 2862 | 2868 | CSG | MISSISSIPPI |

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: DENIED TA

Plugged through: TBG

MAR 29 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
2/8/13
(TECHNICIAN)

✓SK