

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24047-00-00
Spot: NESWNW Sec/Twnshp/Rge: 16-30S-7E
3609 feet from S Section Line, 4298 feet from E Section Line
Lease Name: SCHULZ Well #: 7
County: COWLEY Total Vertical Depth: 3278 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3272		100 SX
SURF	8.625	300		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2013 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM, LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/15/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATING HOLE CLEAN @ 2279', LAYED DOWN TBG. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 2200'-2202' (4 HOLES). RIH ON WIRELINE SHOT SQUEEZE HOLES @ 350'-351' (2 HOLES). RIH W/TBG @ 2229', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON CEMENT 3% CC & DISPLACED IN CASING. PULLED TBG @ 350', COPELAND ACID ESTABLISHED CIRCULATION, & MIXED & PUMPED 155 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 2-15-2013. COPELAND CEMENT TICKET #41796.

Perfs:

Top	Bot	Thru	Comments
3270	3273	OH	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: DENIED TA

Plugged through: TBG

MAR 29 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER
4/22/13
(TECHNICIAN)

JK