

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24074-00-00
Spot: W2NWNWNE Sec/Twnshp/Rge: 35-14S-19W
4950 feet from S Section Line, 2397 feet from E Section Line
Lease Name: YOUNKER Well #: 1
County: ELLIS Total Vertical Depth: 810 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	810		0 SX
SURF	10.75	575		Unknown amount of cement. 10-1984

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 03/18/2013 10:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement.
Perforations: 755'-800'
Operator milled on well for 3 days to get to 575'. Iron in hole. Bad casing.
GPS: 38.79748 -099.40089
4964' FSL 2333' FEL NW NW NW NE

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2013 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Pioneer Perf 2 shot hole at 550'.
Gressel ran in hole with tubing to 570'. Copeland rigged to tubing and mixed and pumped 80 sx cement to circulate cement up 5 1/2" casing and 10 3/4" casing.
Pulled tubing. Topped off 5 1/2" and 10 3/4" casing with 10 sx cement. Hole standing full.

Remarks: COPELAND CEMENTING CO TICKET # 38333

Plugged through: TBG

RECEIVED
MAR 22 2013

KCC WICHITA

District: 04

Signed [Signature]
(TECHNICIAN)

CR

MAR 19 2013