

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20787-00-00
Spot: E2E2E2NW Sec/Twnshp/Rge: 10-31S-41W
3985 feet from S Section Line, 2739 feet from E Section Line
Lease Name: JESSE Well #: 1
County: MORTON Total Vertical Depth: 5775 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5240		WITH 2 SX CMT
COND	20	40		WITH 19 SX CMT
PROD	4.5	5773	1703	WITH 275 SX CMT
SURF	8.625	1552		WITH 645 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/08/2013 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: CIBP @ 5300' WITH 2 SX CMT. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2013 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5240' WITH 2 SX CMT. 1ST PLUG AT 1600' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 598' WITH 50 SX CMT. 3RD PLUG AT 44' TO 0' WITH 15 SX CMT. TOP
OFF WITH 5SX CMT.

Perfs:

Top	Bot	Thru	Comments
5346	5353		MORROW
5327	5329		MORROW

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.


Plugged through: CSG

RECEIVED
MAR 20 2013

KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAR 14 2013
KCC DODGE CITY

