

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19063-00-01
Spot: NESENENW Sec/Twnshp/Rge: 32-26S-6E
4499 feet from S Section Line, 2938 feet from E Section Line
Lease Name: STRAIT Well #: 1
County: BUTLER Total Vertical Depth: 2778 feet

Operator License No.: 7228
Op Name: BRICKLEY, DONALD DBA D & J INVES
Address: 128 N ALLEGHANY PO BOX 107
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2770		75 SX
PROD	5.5	2775		75 SX
SURF	8.25	86		125 SX
SURF	10	195		75 SX

Well Type: EOR UIC Docket No: E12556.1 Date/Time to Plug: 01/29/2013 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JOHN BRICKLEY Company: D&J INVESTMENT Phone: (316) 371-1898

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2013 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2728', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION. MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC., 75# POLY FLAKES, & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2250', PRESSURED CASING @ 100#, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES 250'-251' (4 HOLES). SWEDGED INTO 5 1/2" CSING, CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SX CLASS COMMON CEMENT TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #38483. PLUG DOWN 1-29-2013 @ 4:00 PM.

Perfs:

Top	Bot	Thru	Comments
2775	2778	OH	

RECEIVED
MAR 19 2013

Remarks: DENIED TA / 10 YR

Plugged through: TBG

KCC WICHITA

District: 02

Signed

DUANE KRUEGER
9/02/13 (TECHNICIAN)
* ccto UIC 3/20/13