

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26491-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 36-15S-19W
600 feet from S Section Line, 700 feet from E Section Line
Lease Name: LEGLEITER Well #: 1-36
County: ELLIS Total Vertical Depth: 3680 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	965		730 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/17/2013 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2379

Proposed Plugging Method: Ordered 235 sx 60/40 pozmix - 4% gel cement with 1/4# flo-seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 03/17/2013 12:00 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st plug @3562 w/50 sx
2nd plug @1200 w/25 sx
3rd plug @1010 w/40 sx
4th plug @490 w/80 sx
5th plug @40 w/10 sx

Rathole 30 sx
when well was being drilled:
Well Broke out. Called Bruce Basye on 03/10/13. Pumped 480 sx bar mud, 600 sx cement at 2:00pm. Topped another 30 sx cement at 4:00pm.
03/11/2013- Common cement to circulate. Pat Staab witnessed. Quality Cementing ticket # 6460

Perfs:

Remarks: QUALITY TICKET # 6460

Plugged through: DP

RECEIVED
MAR 22 2013
KCC WICHITA

District: 04

Signed [Signature]
4/6/13 (TECHNICIAN) CM

MAR 19 2013