

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19414-00-00
Spot: SESESW Sec/Twnshp/Rge: 25-14S-15W
482 feet from S Section Line, 3047 feet from E Section Line
Lease Name: HARBAUGH B Well #: 4
County: RUSSELL Total Vertical Depth: 3172 feet

Operator License No.: 31250
Op Name: HUXMAN, RICHARD LEON DBA KSC OIL
Address: PO BOX 567
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	15.5	315		SX
PROD	7	3172		125 SX
SURF	10	762		30 SX

KW

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/04/2013 8:30 AM
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.
Proposal Rcvd. from: LEON HUXMAN Company: KSC OIL Phone: (785) 483-0567

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 750' and 300'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2013 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Had dug out braden head early and found to be full of cement.
03/01/2013-Rigged up and started to clean out bottom. Hit hard at 600'. Had trouble drilling down to 900'.
03/02/2013- Hit hard and could not make any hole. Pulled tubing and shut down.
03/04/2013- Perforated at 750' and 300'. Ran tubing to 900' and pumped 135 sx of cement w/400 # hulls. Lost circulation. Shut down and W.O.C.
Ran tubing back to 300' and pumped 40 sx cement w/150 # hulls.
Cement circulated.
POOH and filled up casing w/10 sx of cement.
Checked on fill up . Down 6'.

GPS: 38.79972 -098.93976

Perfs:

Top	Bot	Thru	Comments
3172	3179		
3026	3036		
3007	3011		
2936	2941		

RECEIVED
MAR 22 2013

Remarks: QUALITY CEMENTING TICKET # 6447

KCC WICHITA

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
3/10/13 (TECHNICIAN)

CM

MAR 12 2013