

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21335-00-00
Spot: N2S2SWNE Sec/Twnshp/Rge: 17-33S-29W
2150 feet from N Section Line, 1980 feet from E Section Line
Lease Name: UTZ Well #: 2A-17
County: MEADE Total Vertical Depth: 5430 feet

Operator License No.: 32211
Op Name: O'BRIEN ENERGY RESOURCES CORP.
Address: 18 CONGRESS ST, STE 207
PORTSMOUTH, NH 03801

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1490		

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 02/18/2013 1:30 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: ROGER PEARSON Company: O'BRIEN ENERGY RESOURCES Phone: (603) 427-2099

Proposed Plugging Method: 1ST PLUG AT 1550' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 02/18/2013 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

****LOST CIRCULATION AT 5382'. DRILLED INTO A FAULT, BIT FELL 6'.**** 1ST PLUG AT 2900' WITH 100 SX CLASS C CMT W/3% CC. WAITED 4 HOURS & TAGGED PLUG AT 4400'. LOADED HOLE WITH MUD. 2ND PLUG AT 1550' WITH 50 SX CMT. 3RD PLUG AT 550' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: DP

RECEIVED
MAR 20 2013

KCC WICHITA

District: 01

Signed _____

Ken Jehlik
2/18/13

(TECHNICIAN)

RECEIVED
MAR - 6 2013
KCC DODGE CITY