

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-00474-00-00  
Spot: SWSWSWNE Sec/Twnshp/Rge: 9-35S-41W  
2799 feet from S Section Line, 2505 feet from E Section Line  
Lease Name: HOWARD C Well #: 1  
County: MORTON Total Vertical Depth: 2365 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2364	0	WITH 550 SX CMT
SURF	8.625	365		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/08/2013 11:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 350# HULLS & 30 SX CMT. SPACER TO 450'. PLUG FROM 450' TO 0' WITH 55 SX CMT. USE 15 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 03/08/2013 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 350# HULLS & 30 SX CMT TO 2346'. (APPROXIMATE CMT TOP @ 1650')  
SPACER TO 450'. TAG WITH SLICK LINE FLOAT. PUMP 55 SX CMT FROM 450' TO  
0'. PRESSURE TO 500#. HOLDING. PUMP 5 SX CMT DOWN THE ANNULUS.  
PRESSURE TO 300#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2342	2346		
2328	2335		
2306	2324		
2280	2296		
2270	2274		
2260	2266		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED  
MAR 20 2013

KCC WICHITA

District: 01

Signed

*[Handwritten Signature]*  
4/02/13

(TECHNICIAN)

RECEIVED

MAR 14 2013

KCC DODGE CITY