

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20349-00-00
Spot: NWNWSENV Sec/Twnshp/Rge: 13-34S-40W
1325 feet from N Section Line, 1414 feet from W Section Line
Lease Name: STUART A Well #: 2
County: MORTON Total Vertical Depth: 3345 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2800		WITH 3 SX CMT
PROD	4.5	3034	640	WITH 275 SX CMT
SURF	8.625	545		WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/20/2013 9:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 2800' WITH 3 SX CMT. 30 SX PLUG AT FREEPOINT. PLUG AT 1720' WITH GEL & 50 SX CMT. PLUG AT 60' WITH 645 SX CMT. PLUG AT 50' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 03/20/2013 3:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 2800' WITH 3 SX CMT. COLLAR SPLIT SHOT @ 1720'. INJECTION RATE 1200# DECREASING TO 700#. PUMP 50 SX CMT (30 SX CMT OUTSIDE 4 1/2" CASING LEAVING 20 SX CMT INSIDE THE 4 1/2" CASING). PLUG AT 690' WITH 65 SX CMT. TAG TOC. PLUG AT 50' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2928	2938		
2909	2916		
2893	2897		
2870	2883		
2850	2856		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 27 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed



(TECHNICIAN)

RECEIVED

MAR 22 2013

KCC DODGE CITY

Form CP-2/3

Handwritten initials