

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20208-00-00
Spot: SESWNENE Sec/Twnshp/Rge: 22-20S-36W
1160 feet from N Section Line, 765 feet from E Section Line
Lease Name: GERTSBERGER Well #: 1
County: WICHITA Total Vertical Depth: 5228 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	267		WITH 225 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/12/2013 5:00 AM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Rcvd. from: CARLOS FABELA Company: H2 DRILLING LLC Phone: (620) 636-2090

Proposed Plugging Method: 1ST PLUG AT 2260' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 03/12/2013 7:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2260' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED
MAR 20 2013

KCC WICHITA

District: 01

Signed Eric MacLaren
4/10/13 (TECHNICIAN)

RECEIVED

MAR 14 2013

KCC DODGE CITY