

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20818-00-01  
Spot: E2SWNW Sec/Twnshp/Rge: 29-5S-36W  
1980 feet from N Section Line, 990 feet from W Section Line  
Lease Name: BRINEY TRUST B Well #: 1  
County: RAWLINS Total Vertical Depth: 4740 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		4464		
PROD	4.5	4726		160 SX
SURF	8.625	342		230 SX
T1	2.375	4609		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/14/2013 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.  
8 5/8" surface casing set at 342' w/230 sx cement. 4 1/2" production casing set at 4726' w/160 sx cement.  
TD 4740'. PBD 4637'. Perforations: 4555'-4585' and 4184'-4456'. Packer stuck in 4 1/2" casing at 4460' with 2 tubing joints on top and 4 tubing joints below packer, seating nipple and mud anchor.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/14/2013 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 3010' and 2200'.  
Ran tubing to 4400'. Pumped 110 sx cement mixed with 150 # hulls. 50 sx cement without hulls and 60 sx cement with 150 # hulls.  
Pulled tubing to 3100' and pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 1550' and pumped 160 sx cement w/200 # hulls. Cement to surface.  
Pulled tubing to surface. Connected to 4 1/2" production casing. Pumped 20 sx cement.  
Connected to 8 5/8" surface casing. Pumped 60 sx cement.

GPS: 39.59209N -101.39129W

Perfs:

Top	Bot	Thru	Comments
4565	4571		
4555	4585		
4526	4529		
4503	4507		
4289	4292		
4277	4279		
4184	4456		

Remarks: ALLIED CEMENT TICKET # 60,056

Plugged through: TBG

RECEIVED

MAR 13 2013

KCC WICHITA

District: 04

Signed Darrel Dipman  
4/2/13 (TECHNICIAN) CM

FEB 13 2013