

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05445-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 14-13S-17W  
2310 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: KARLIN Well #: 4  
County: ELLIS Total Vertical Depth: 3532 feet

Operator License No.: 33905  
Op Name: ROYAL DRILLING INC  
Address: 719 WITT AVE PO BOX 342  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3438		150 sx
PROD	5.5	3525		125 SX
SURF	8.625	155		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/08/2013 8:30 AM  
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC  
Proposal Rcvd. from: JOHN L DRISCOLL Company: ROYAL DRILLING INC Phone: (785) 483-6446

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
CIBP at 3400'  
Squeezed 762'-1693' w/200 sx cement  
Squeezed 900'-950' w/200 sx cement  
Casing leak at 1600'.  
  
GPS: 38.92123 -099.17716  
2318' FSL 2346' FEL NW NW NW SE

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/08/2013 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Royal Drilling ran in hole with tubing to 3400'. Allied rigged to tubing and mixed and pumped 125 sx cement w/300 # hulls mixed in.  
Pulled tubing to 1650'. Allied rigged to tubing and mixed and pumped 60 sx cement w/200 # hulls mixed in to circulate cement up 4 1/2" liner.  
Pulled tubing. Rigged to 4 1/2" liner with a swedge and pumped 15 sx cement to pressure with 300 psi and 300 psi shut in pressure.  
Rigged to 8 5/8" casing. Pumped 15 sx cement to pressure with 250 psi and 150 psi shut in pressure.

Remarks: ALLIED CEMENTING OIL AND GAS SERVICES LLC TICKET # 56877


Plugged through: TBG

RECEIVED  
MAR 18 2013

KCC WICHITA

District: 04

Signed

  
4/10/13 (TECHNICIAN)

CM

MAR 11 2013