

*\* OK TO PLUG - PLUG BY PAULS WIN*  
API Well Number: 15-073-21744-00-01 *5 YR. CUTOFF.*  
Spot: SENESEW Sec/Twnshp/Rge: 32-24S-11E  
1650 feet from S Section Line, 2910 feet from E Section Line  
Lease Name: WIGGENS Well #: 5  
County: GREENWOOD Total Vertical Depth: 1710 feet

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

Operator License No.: 6560  
Op Name: SNYDER, K. LANCE  
Address: 205 E JACKSON PO BOX 166  
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1749		
SURF	8.625	89		

Well Type: EOR UIC Docket No: E20966.1 Date/Time to Plug: 01/23/2008 8:00 AM  
Plug Co. License No.: 32147 Plug Co. Name: K.E. SNYDER CO., LLC  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' cement plug @ 1710' 50' cement plug 2 800' 150' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/25/2008 3:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

shot casing @ 800' & 150' , ran tubing to 1710' pumped 5 sxs cement, pulled tubing to 800'  
pumped 12 sxs cement, pulled tubing to 150' pumped 40 sxs cement to surface.

RECEIVED  
MAR 15 2013  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mik [Signature]  
4/18/13 (TECHNICIAN)

*\* cc to UIC 3/20/13*