

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20266-00-00
Spot: N2N2SWNE Sec/Twnshp/Rge: 35-22S-3W
3780 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SCHRAG Well #: D-1
County: HARVEY Total Vertical Depth: 3298 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3298		0 SX
SURF	8.625	250		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/04/2013 12:00 AM
Plug Co. License No.: 5399 Plug Co. Name: TREK AEC, LLC
Proposal Rcvd. from: BARRY CONSIDINE Company: _____ Phone: (620) 755-2744

Proposed Plugging Method: As per Kansas Corporation Commission Rules and Regulations, as per their recommendations.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 02/06/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

2/5/13 PUMPED 35 SX CEMENT DOWN TUBING FOR BOTTOM PLUG. SHOT TUBING OFF AT 420', PULLED TUBING. PRESSURE TESTED CASING, HELD. RAN WIRELINE TO 390' 4 SHOTS INTO 4.5 CASING. PUMPED 185 SXS CEMENT TO BRING CEMENT AROUND INSIDE OF SURFACE PIPE. 2/6/13 CUT HEAD OFF, CEMENT FELL BACK TO 90' BETWEEN 8 5/8" AND 4.5" CASING, FELL BACK 140' INSIDE 4.5", TOOK 40 SX CEMENT TO BRING TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3160	3210		

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 29 2013

Remarks: COPELAND CEMENTING OUT OF BURRTON, 60/40 4% POS MIX, TICKET # 41786

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed B. J. Hope
4/6/13 (TECHNICIAN)