

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25640-00-00
Spot: SWNESENE Sec/Twnshp/Rge: 14-16S-12W
3626 feet from S Section Line, 347 feet from E Section Line
Lease Name: FELTES Well #: 2
County: BARTON Total Vertical Depth: 3571 feet

Operator License No.: 6357
Op Name: WEBCO OIL COMPANY, INC.
Address: 2136 NE 90 AVE
HOISINGTON, KS 67544

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP | | 3350 | | |
| PKR | | 3378 | | |
| PROD | 5.5 | 3453 | 1554 | 170 SX |
| SURF | 8.625 | 431 | | 225 SX |
| T1 | 2.875 | 3378 | | |

Well Type: SWD UIC Docket No: D31136.0 Date/Time to Plug: 02/20/2013 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: N.R. WEBER Company: WEBCO OIL Phone: (620) 587-3539

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/20/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with 5 sx cement.
Cut casing off at 1539'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls.
Pulled casing to 500'. Circulated cement to surface with 150 sx cement w/100 # hulls.
Pulled casing. Topped off with 20 sx cement.

GPS: 38.66221 -098.60976

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3453 | 3571 | | |
| 3240 | 3246 | | |
| 3210 | 3214 | | |
| 3152 | 3156 | | |
| 3100 | 3104 | | |
| 3071 | 3075 | | |
| 2908 | 2914 | | |

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

RECEIVED
MAR 13 2013

KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

✓ cc to UIC 3/12/13

CM

MAR 06 2013