

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23364-00-00
Spot: N2NENW Sec/Twnshp/Rge: 6-34S-10W
341 feet from N Section Line, 1979 feet from W Section Line
Lease Name: JAHAY Well #: 3
County: BARBER Total Vertical Depth: 5130 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5061	3380	WITH 250 SX CMT
SURF	10.75	226		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/27/2013 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 35 SX CMT & 250# HULLS PLUG AT 600' WITH 50 SX CMT. PLUG AT 250' WITH 75 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/27/2013 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP DOWN 4 1/2" CASING WITH 250# HULLS & 35 SX CMT. DISPLACED PLUG TO 4500'. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 75 SX CMT. 3RD PLUG AT 42' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4768	4790		MISSISSIPPIAN
4700	4744		MISSISSIPPIAN
4677	4692		MISSISSIPPIAN
4638	4672		MISSISSIPPIAN
4616	4790		MISSISSIPPIAN

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 01 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Stephen J. Pfeifer
4/8/13 (TECHNICIAN)

RECEIVED

MAR 28 2013

KCC DODGE CITY