

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23651-00-00
Spot: NWSWNENE Sec/Twnshp/Rge: 14-35S-13W
933 feet from N Section Line, 1133 feet from E Section Line
Lease Name: MYERS Well #: 1
County: BARBER Total Vertical Depth: 5700 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4805 | | |
| PROD | 5.5 | 5251 | 3130 | WITH 200 SX CMT |
| SURF | 10.75 | 251 | | WITH 240 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/25/2013 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4370' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 75 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/25/2013 6:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP DOWN 5 1/2" CASING WITH 250# HULLS & 35 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 75 SX CMT. 3RD PLUG AT 42' WITH 25 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4892 | 4930 | | |
| 4886 | 4930 | | |
| 4424 | 4430 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 01 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

MAR 28 2013

KCC DODGE CITY

Signed

Stephen A. Pfeifer
4/02/13
(TECHNICIAN)

APR 01 2013