

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20250-00-02
Spot: NWNESW Sec/Twnshp/Rge: 12-10S-24W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SE GANO UNIT Well #: 2-2
County: GRAHAM Total Vertical Depth: 4080 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4010		
PROD	4.5	4067		200 SX
SURF	8.625	203		140 SX

Well Type: EOR UIC Docket No: E24173.2 Date/Time to Plug: 01/15/2013 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
DV Tool at 2137' w/500 sx cement.
Perforations from 3823' to 3828', 3854' to 3858', 3865' to 3870' 3905' to 3910', 3958' to 3964', 3980' to 3986', 3993' to 4000', 4015' to 4019'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/15/2013 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3600' and pumped 150 sx cement w/300 # hulls.
Pulled tubing to 1900' and pumped 130 sx cement w/200 # hulls. Good circulation of cement.
Pulled tubing out of hole and topped off casing with 20 sx cement. Hole standing full.
Tied on to back side. Squeezed with 15 sx cement. Shut in pressure 100 psi.

GPS: 39.19634 -099.95345

Perfs:

Top	Bot	Thru	Comments
4015	4019		
3993	4000		
3980	3986		
3958	3964		
3905	3910		
3865	3870		
3854	3858		
3823	3828		

Remarks: SWIFT CEMENT COMPANY TICKET # 23744

KCC WICHITA

Plugged through: TBG

District: 04

Signed

[Signature]
2/14/13
KCC to MC 1/23/13
(TECHNICIAN)

CM

JAN 17 2013