

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20016-00-00  
Spot: NESENE Sec/Twnshp/Rge: 17-21S-1W  
1650 feet from N Section Line, 330 feet from E Section Line  
Lease Name: GOERING P Well #: 1  
County: MCPHERSON Total Vertical Depth: 3332 feet

Operator License No.: 5631  
Op Name: LOEWEN OPERATOR, INC.  
Address: 208 S MAIN PO BOX 335  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3025		
PROD	5.5	3327		75 SX
SURF	8.625	135		95 SX

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2013 9:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: VAN BACON Company: \_\_\_\_\_ Phone: (620) 654-7786

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/12/2013 1:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

RAN TUBING DOWN TO 2880' SET A 30 SX PLUG OF 60/40 4%, TRIPPED OUT TO 300' PUMPED CEMENT TO SURFACE WITH 60 SX OF 60/40 4%. RAN 1" DOWN THE BACKSIDE TO A DEPTH OF 250' PUMPED 140 SX TO SURFACE OF 60/40 4% WITH A 10 SX TOP OF. CHECKED TOP PLUG 3/15 WAS STILL AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
2964	2968		MISSISSIPPI
2942	2948		MISSISSIPPI

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: CEMENT TICKET #38320 COPLAND GREAT BEND

MAR 29 2013

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed Hunter Clark (TECHNICIAN)  
cc to MIC 4/02/13  
4/04/13