

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24679-00-00
Spot: E2NENWSE Sec/Twnshp/Rge: 24-17S-26W
2299 feet from S Section Line, 1430 feet from E Section Line
Lease Name: POPP 'A' Well #: 4
County: NESS Total Vertical Depth: 4370 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4300		WITH 2 SX CMT
DVT	4.5	1756		WITH 335 SX CMT
PROD	4.5	4351	0	WITH 200 SX CMT
SURF	8.625	280		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2013 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ED MONDERO Company: PICKRELL DRILLING Phone: (620) 793-2315

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT. FILL 4 1/2" CASING WITH CMT FROM DV TOOL TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2013 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4300' WITH 2 SX CMT. RUN TBG TO 1810' & PUMP 165 SX CMT. CMT CIRCULATED TO SURFACE. TIE ONTO BACKSIDE & PUMP 35 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4368	4370		
4366	4368		
4351	4366		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

MAR 27 2013

KCC DODGE CITY

Signed

Michael Maier
4/24/13

(TECHNICIAN)

BAW