

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-21410-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 10-23S-35W
4030 feet from S Section Line, 4030 feet from E Section Line
Lease Name: MILLER K Well #: 2
County: KEARNY Total Vertical Depth: 2850 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2849	0	WITH 485 SX CMT
SURF	8.625	601		WITH 270 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/28/2013 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 02/28/2013 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 300# HULLS & 40 SX CMT TO 2654'. SPACER TO 1000'. TAG WITH SLICKLINE FLOAT. PLUG AT 1000' WITH 25 SX CMT. SPACER TO 600'. TAG WITH SLICKLINE FLOAT. PLUG AT 600' WITH 25 SX CMT. SPACER TO 40'. PUMP 5 SX CMT AT 40-0'. PRESSURE TO 500#. PUMP 10 SX CMT DOWN ANNULUS TO 500#.

Perfs:

Top	Bot	Thru	Comments
2652	2654		
2610	2612		
2595	2597		
2568	2570		
2554	2556		
2540	2542		
2502	2506		

Remarks: USED COMMON CEMEBNT BY SARGENT LILLARD.

Plugged through: CSG

RECEIVED
MAR 08 2113
KCC WICHITA

District: 01

RECEIVED
MAR - 5 2013
KCC DODGE CITY

Signed Ken Jehlik
3/18/13 (TECHNICIAN)