

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21087-00-00  
Spot: SESE Sec/Twnshp/Rge: 3-24S-21W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: GLEASON Well #: 1  
County: HODGEMAN Total Vertical Depth: 4682 feet

Operator License No.: 31093  
Op Name: BECKER OIL CORPORATION  
Address: PO BOX 1150  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4350		WITH 2 SX CMT
CIBP		4594		
PROD	4.5	4681	0	WITH 125 SX CMT
SURF	8.625	386		WITH 240 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/14/2013 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JERRY AILEY Company: BECKER OIL Phone: (620) 287-4724

Proposed Plugging Method: SET CIBP @ 4350' WITH 2 SX CMT. PERFORATE @ 600' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/14/2013 12:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4350' WITH 2 SX CMT. LOAD HOLE WITH FLUID & PRESSURE TO 500#. PERFORATE CASING AT 600' & PUMPED 150 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4633	4640		
4418	4425		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
FEB 28 2013  
KCC DODGE CITY

Signed [Signature]  
9/06/13  
(TECHNICIAN)

RECEIVED  
MAR 05 2013  
KCC WICHITA

Form CP-2/3

[Handwritten initials]