

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20873-00-00
Spot: N2NWSE Sec/Twnshp/Rge: 28-27S-22W
2305 feet from S Section Line, 2000 feet from E Section Line
Lease Name: RIEGEL 28AD Well #: 1
County: FORD Total Vertical Depth: 5200 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	394		WITH 275 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/29/2013 11:30 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 540' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 01/30/2013 1:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 540' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Eric MacLaren
2/7/13 (TECHNICIAN)

RECEIVED
FEB - 6 2013
KCC DODGE CITY

RECEIVED
FEB 08 2013
KCC WICHITA

AWY