

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23796-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 21-23S-13W
2100 feet from N Section Line, 1100 feet from E Section Line
Lease Name: TERREAU Well #: 1
County: STAFFORD Total Vertical Depth: 3905 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	328		WITH 300 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/15/2013 10:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: GALEN ROACH Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 3898' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN
Date/Time Plugging Completed: 04/15/2013 2:15 PM

Witness Type: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 3898' WITH 50 SX CMT. 2ND PLUG AT 787' WITH 50 SX CMT. 3RD PLUG AT 378' WITH 50 SX CMT. 4TH PLUG AT 62' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: DP

District: 01

Signed Richard M. Lacey
4/23/13 (TECHNICIAN)

RECEIVED
APR 16 2013
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

APR 22 2013
CONSERVATION DIVISION
WICHITA, KS