

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-26819-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 6-32S-13E
3212 feet from S Section Line, 2201 feet from E Section Line
Lease Name: MCGEE Well #: 7-6
County: CHAUTAUQUA Total Vertical Depth: 1646 feet

Operator License No.: 34779
Op Name: LR ENERGY, INC.
Address: 8150 N. CENTRAL EXPY, STE 1605
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1646		170 SX
SURF	8.625	42		10 SX
T1	2.375	1425		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 01/23/2013 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JACOB MCCLAIN Company: _____ Phone: (620) 627-2499

Proposed Plugging Method: Spot 50' cement plug on bottom. Gel spacer to 1322. Pump 80' cement plug over perforations. Pump gel spacer to 275'. Pump 275' cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2013 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2' to 1635' gelled hole and spotted 10 sack plug. Pulled up to 1325' and spotted 45 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 2" and topped well off. A total of 80 sacks of 60/40 pozmix cement to plug this well.

Perfs:

Top	Bot	Thru	Comments
1318	1321		also known as the Cr
1300	1301		
1253	1260		
1252	1260		
1242	1243		

RECEIVED

APR 09 2013

KCC Chanute Dist. #3

DS

Remarks:


RECEIVED
KANSAS CORPORATION COMMISSION

Plugged through: TBG

APR 11 2013

District: 03

Signed


4/29/13 (TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS