

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21451-00-00  
Spot: SENE Sec/Twnshp/Rge: 30-23S-22W  
1930 feet from N Section Line, 518 feet from E Section Line  
Lease Name: COOK Z Well #: 1  
County: HODGEMAN Total Vertical Depth: 4698 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: PO BOX 544 N HWY 283  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4701	1850	WITH 125 SX CMT
SURF	8.625	625		WITH 345 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/03/2012 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC *2013*  
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RTIH TO 4550' WITH 40 SX CMT & 200# HULLS. PLUG AT 1570' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/02/2013 3:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

RTIH TO 4554' WITH 50 SX CMT & 200# HULLS. 1ST PLUG AT 1570' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4624	4627		
4612	4616		
4605	4608		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

RECEIVED  
JAN 07 2013  
KCC WICHITA

District: 01

Signed [Signature]  
01/04/13 (TECHNICIAN)

RECEIVED  
JAN - 3 2013 *MP*  
KCC DODGE CITY

*RDW*