

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22052-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 8-27S-12W  
3007 feet from S Section Line, 363 feet from E Section Line  
Lease Name: SMITH Well #: 1-8  
County: PRATT Total Vertical Depth: 4269 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4200		
PROD	4.5	4253	2110	WITH 225 SX CMT
SURF	10.75	262		WITH 250 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/15/2013 12:00 PM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-9571

Proposed Plugging Method: SANDED TO 4050' WITH 4 SX CMT. PLUG AT 660' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/15/2013 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4030' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 661' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 297' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4146	4166		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

*Stephen J. Pape*  
2/27/13  
(TECHNICIAN)

RECEIVED

JAN 17 2013

KCC DODGE CITY

RECEIVED  
JAN 24 2013  
KCC WICHITA

*AMC*