

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25802-00-00

Spot: SENESESW

Sec/Twnshp/Rge: 16-20S-11W

785 feet from S Section Line, 2630 feet from W Section Line

Lease Name: ROSCO

Well #: 2

County: BARTON

Total Vertical Depth: 3328 feet

Operator License No.: 33964

Op Name: PROLIFIC RESOURCES LLC

Address: 2725 DRY CRK RD
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	303		180 sx

Well Type: DH

UIC Docket No:

Date/Time to Plug: 01/14/2013 12:00 AM

Plug Co. License No.: 33905

Plug Co. Name: ROYAL DRILLING INC

Proposal Rcvd. from: SHILOW

Company: ROYAL DRILLING INC

Phone: (785) 324-0030

Proposed
Plugging
Method:

Ordered 210 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE

WitnessType: NONE

Date/Time Plugging Completed: 01/14/2013 6:00 PM

KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfs:

1st plug @3280 w/50 sx
2nd plug @520 w/25 sx
3rd plug @330 w/80 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

District: 04

Signed

Bruce D Basye
1/14/13
(TECHNICIAN)

CR

RECEIVED
FEB 18 2013

KCC WICHITA

FEB 01 2013