

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21782-00-00  
Spot: W2NWSW Sec/Twnshp/Rge: 23-29S-7W  
1980 feet from S Section Line, 330 feet from W Section Line  
Lease Name: VORAN Well #: A1  
County: KINGMAN Total Vertical Depth: 4285 feet

Operator License No.: 32215  
Op Name: RAKESTRAW BROS., L.L.C  
Address: 4566 NE PARALLEL RD  
EL DORADO, KS 67042

| String | Size  | Depth (ft) | Pulled (ft) | Comments    |
|--------|-------|------------|-------------|-------------|
| PKR    | 5.5   | 4073       |             |             |
| PROD   | 5.5   | 4278       | 2600        | 125 SXS CMT |
| SURF   | 8.625 | 258        |             | 175 SXS CMT |
| T1     | 2.375 | 4215       |             |             |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2012 8:00 AM  
Plug Co. License No.: 34235 Plug Co. Name: AMIGOS WELL SERVICE INC.  
Proposal Rcvd. from: EDGAR SANCHEZ Company: AMIGOS WELL SERVICE Phone: (620) 388-6229

Proposed Plugging Method: CIBP ABOVE PERFS & CAP WITH 2 SKS CMT. RECOVER PIPE. 35 SX 1100', 35 SX 700', CIRC 310'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/28/2012 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH A CIBP AT 4100' & CAPPED WITH 2 SKS CMT. THE CASING WAS RECOVERED FROM 2600' & PULLED TO 1100' WHERE 35 SXS OF CMT WAS SPOTTED. PULLED CASING TO 660' & SPOTTED 35 SX CMT. PULLED CASING TO 340' & CIRC'D CMT TO SURFACE.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4178 | 4184 |      | CSG      |
| 4142 | 4152 |      | CSG      |


Remarks: ALLIED CEMENT. 60/40 4% GEL.

Plugged through: CSG

RECEIVED  
JAN 07 2013  
KCC WICHITA

District: 02

Signed \_\_\_\_\_

  
(TECHNICIAN)

