

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20655-00-01
Spot: NENESE Sec/Twnshp/Rge: 10-28S-16W
2301 feet from S Section Line, 359 feet from E Section Line
Lease Name: FANKHAUSER D Well #: 1
County: KIOWA Total Vertical Depth: 4820 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4819	2040	WITH 175 SX CMT
SURF	8.625	421		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/16/2013 2:15 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 300# HULLS & 75 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2013 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP DOWN 4 1/2" CASING WITH 300# HULLS & 75 SX CMT. 1ST PLUG AT 1090' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4732	4742		
4708	4716		
4692	4696		
4654	4671		
3474	3477		

RECEIVED
JAN 24 2013
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Steve J. Pfeifer
8/16/13
(TECHNICIAN)

RECEIVED
JAN 17 2013
KCC DODGE CITY