

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21409-00-00  
Spot: SESWSWSW Sec/Twnshp/Rge: 10-25S-16W  
308 feet from S Section Line, 353 feet from W Section Line  
Lease Name: BREITENBACH Well #: 3  
County: EDWARDS Total Vertical Depth: 4440 feet

Operator License No.: 32713  
Op Name: SAND POINT LLC  
Address: 5909 NW EXPRESSWAY, STE 490  
OKLAHOMA CITY, OK 73132

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4270		WITH 2 SX CMT
PROD	5.5	4439	2208	WITH 100 SX CMT
SURF	8.625	395		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/14/2012 12:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4270' WITH 2 SX CMT. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/15/2012 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP@ 4270' WITH 2 SX CMT. 12/14/12: 1ST PLUG AT 1053' WITH 15 SX GEL & 50 SX CMT. NO CIRCULATION. 12/15/12: TOC @ 500'. RTIH TO 421'. PUMPED 15 SX GEL, 300# HULLS & ESTABLISHED CIRCULATION. PUMPED 50 SX CMT WITH 100# HULLS. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4374	4382		
4333	4352		
4313	4318		

RECEIVED  
JAN 07 2013  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Kenny Sullivan (TECHNICIAN)  
12/15/12

RECEIVED  
DEC 27 2012  
KCC DODGE CITY

AWJ