

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20012-00-00  
Spot: W2NWSE Sec/Twnshp/Rge: 9-33S-41W  
1980 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 21-1A  
County: MORTON Total Vertical Depth: 5100 feet

Operator License No.: 34832  
Op Name: SCOUT ENERGY MANAGEMENT LLC  
Address: 14400 MIDWAY RD  
DALLAS, TX 75244

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1100		
PROD	4.5	5099	0	WITH 200 SX CMT
SURF	8.625	1005		WITH 525 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/09/2013 10:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: GILBERTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/10/2013 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 75 SX CMT @ 4950'. SET CIBP @ 1100'. TEST CASING TO 600#. HOLDING.  
PERFORATE @ 1055'. INJECTION RATE 2 BPM @ 100 PSI. SQUEEZE 80 SX CMT  
THROUGH PERFS TO 500#, LEAVING 25 SX CMT INSIDE 4 1/2" CASING.  
PERFORATE @ 550'. CIRCULATE CMT TO SURFACE WITH 145 SX CMT LEAVING 4  
1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5051	5053		
5038	5041		

Remarks: USED CLASS C COMMON CEMENY BY ORR ENTERPRISES.

Plugged through: CSG

RECEIVED  
JAN 18 2013  
KCC WICHITA

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
JAN 15 2013  
KCC DODGE CITY

Form CP-2/3

Remarks: ALLIED

Plugged through: DP

RECEIVED  
FEB 05 2013  
KCC WICHITA

District: 04

Signed [Signature]  
(TECHNICIAN)

JAN 25 2013

Form CP-2/3